



# ***JAXA Activities for SSPS Research***

- ***Commercial Models of Space Solar Power Systems (SSPS)***
- ***Ground Demonstration Experiments***
  - ***Wireless Power Transmission(Microwave and Laser)***
  - ***Large Space Structure***
- ***Space Demonstration Experiments***
- ***Roadmap towards Commercial SSPS***




***June 2011***


# ***Commercial SSPS Concepts Currently Studied in Japan***



***Basic  
Microwave-type  
Model  
(USEF/METI)***



***Advanced  
Microwave-type  
Model  
(JAXA/MEXT)***




***Laser Model  
(JAXA/MEXT)***

***USEF/METI: Unmanned Space Experiment Free Flyer/ Ministry of Economy, Trade and Industry  
JAXA/MEXT: Japan Aerospace Exploration Agency/ Ministry of Education, Culture, Sports, Science and Technology***






# SSPS Key Tasks Required for Near-term Research

<i>Technology field</i>	<i>Specific Technology/Research</i>
<i>Microwave power transmission</i>	<i>Precise microwave beam pointing</i>
	<i>High efficiency power conversion between dc and rf</i>
	<i>Interaction between high-power beam and ionosphere</i>
<i>Laser power transmission</i>	<i>Direct laser generation from sunlight in a high efficiency</i>
	<i>Precise laser beam pointing</i>
	<i>High efficiency power conversion between laser and dc</i>
	<i>Transmission efficiency through atmosphere</i>
<i>Large space structure</i>	<i>Deployment of panel structure typically 0.1 m thick</i>
	<i>Deployment of light-weight structure typically 300 g/m<sup>2</sup></i>
<i>Solar power collecting mirror</i>	<i>High magnification sun light collector</i>
	<i>Filter coatings for uv and ir light</i>





# Development Steps towards Commercial SSPS

<b>Phase</b>	<b>Ground Demonstration</b>	<b>Small Scale Demonstration in Space</b>	<b>Large Scale Demonstration in Space</b>	<b>Small Plant in Space</b>	<b>Large Plant in Space</b>
<b>Transmission</b>	<b>Ground</b>	<b>LEO to Ground</b>	<b>LEO to Ground</b>	<b>1000 km to Ground</b>	<b>GSO to Ground</b>
<b>Range</b>	<b>50-500 m</b>	<b>400 km</b>	<b>400 km</b>	<b>1000 km</b>	<b>36000 km</b>
<b>Power Level</b>	<b>kW level</b>	<b>kW level</b>	<b>100 kW level</b>	<b>2 MW level</b>	<b>200 MW level</b>
<b>Structure Scale</b>	<b>several m</b>	<b>several m</b>	<b>20 m</b>	<b>100 m</b>	<b>500 m</b>
<b>Power at Receiver</b>	<b>several hundreds Watt</b>	<b>—</b>	<b>10kW</b>	<b>1.8MW</b>	<b>160MW</b>
<b>System( in case of Basic Model)</b>					

A landscape photograph showing a grassy field in the foreground. On the left side of the field, there is a small, single-story grey building with a flat roof and a small window. A tall, thin white pole stands next to the building. In the background, there is a large, rolling hill covered in dense green forest. The sky is overcast with grey clouds. The text "Ground Demonstration Experiment" is overlaid in the center of the image in a bold, orange, italicized font.

# *Ground Demonstration Experiment*



# ***Microwave Power Transmission Experiment on Ground***


## ***General Concept***

- Transmission of a kilowatt-level microwave to a rectenna located typically at 50 m apart from the phased array transmitting antenna***
- Beam direction control by a pilot signal from the rectenna site***

## ***Objectives***


- to establish technologies to control a microwave power beam directing at a target rectenna,***
- to establish technical readiness for the space experiment in the near future.***

# Microwave Power Transmission Demonstration



**Rectenna output power will be used to operate household electric appliances for public demonstration.**

# Laser Power Transmission Experiment on Ground




Laser Power Transmission experiment(200W class) at Kakuta/JAXA




Laser power generation experiment(100W class)




# Large Space Structure (Thick Panel and Thin Mirror)





*Demonstration of Automatic Deployment*



*Configuration of automatic panel builder.*



*Large mirror consisting of a large number of segment mirrors (non-monolithic mirror)*




*Measurement of mirror surface roughness and evaluation of reflectance performance in a km range*

A white rocket is shown in flight, angled upwards from the bottom center towards the top left. The rocket has a yellow band with a red circle and the word "NIPPON" in black. Below the band, the word "HYPER" is written in blue. The background is a high-angle aerial view of a rugged coastline with dark blue water, white waves, and green hills. The text "Flight Demonstration Experiment" is overlaid in orange, italicized font across the middle of the image.

# *Flight Demonstration Experiment*

# ***Two Possible Platforms for SSPS Wireless Power Transmission Experiment in the Near Future***



***JAXA small scientific satellite to be launched by next-generation solid propellant rocket, Epsilon launch vehicle. 500 kg class satellite. Payload weight 200 kg typical. First flight will be in 2013.***



***Japanese Experiment Module Kibo on the International Space Station (ISS), for science and technology research. Payload weight 500 kg typical.***



# *Experiment on Small Satellite*



*Orbit: Low Earth Orbit (370 km)*

*Satellite Weight: 500 kg*

*Mission Weight: 200 kg*


*Attitude Control: 3-axis Stabilization*

*Transmission Power: 3.8 kW*




# Experiment Configuration

Mode A



Mode B



# ***Laser Power Transmission Experiment from JEM (an example)***

***International Space Station JEM***



***Transmitter  
1 kW, 1.06  $\mu\text{m}$   
20 cm  $\Phi$  Optics***

***Laser Beam***

***Divergence 15  $\mu\text{rad}$   
Pointing 1  $\mu\text{rad}$***

***Receiver  
10 m  $\Phi$  Area  
200 W Output***


***Pilot Beam***

***Photovoltaic Cell Array***



Research Phase

Roadmap



# Summary and Conclusion

- *Three commercial SPS models currently studied in Japan; basic microwave-type, advanced microwave-type, and laser type, are introduced.*
- *As the first demonstration on the ground towards the commercial models, kW-class wireless power transmission experiments with 50-500 m range and deployment experiment for large space structure are now under way and will be completed within 2-3 years.*
- *Immediately after the ground demonstration experiment, we will conduct a small-scale experiment in orbit to transmit a 1 kW class wireless power to the ground.*
- *This approach is in accordance with the basic plan on space development by the government's space development strategy headquarter in Japan.*